

# Table of Contents

# Written Specifications

## ■ Written Specifications

Security Solutions.....	1
Storm Protection.....	5
Sun Protection - Habitat Screens .....	9
Sun Protection - Rollshutters.....	13
Energy Efficiency.....	16
Insect Protection.....	21
Vandalism Protection .....	25

## Content Library

### ■ Rollshutter Curtain Profiles and Habitat Screen™ Fabric

HQ Macro.....	29
SHIELD Mini.....	29
SAFE Mini.....	29
SHIELD Standard .....	29
Tuffscreen .....	29
SunTex 90 .....	30
SunTex 95 .....	30

### ■ Guide Rails

Rollshutters PRO and PRO-40 Rail.....	31
Rollshutters SAFE and SAFE-40 Rails .....	31
Habitat Screens™ PRO Rail with Edge Retention Insert .....	31

### ■ Bottom Profile

Habitat Screen™ Bottom Profile .....	31
--------------------------------------	----

### ■ Sill

Rollshutter SAFE U-Sill: .....	32
Rollshutter & Habitat Screen™ L Sill: .....	32

### ■ Build-Up

Rollshutter & Habitat Screen™ Build Up: .....	32
---	----

### ■ Panel Box Housing

Rollshutter Panel Boxes .....	32
Habitat Screen Panel Boxes.....	32

### ■ Colour Selection

Rollshutter Colour Selection:.....	33
Habitat Screen™ Colour Selection .....	33

### ■ Operation

Manual Crank with Gear Operation: .....	33
Standard Limit Motor Operation.....	33
Somfy RTS Motor Operation .....	34
Somfy RTS Motor with Sun Sensor Operation.....	34
Rollshutter with Manual Override .....	34

### ■ Locking Devices (Rollshutters Only)

No Lock Required.....	35
Manual Sliding Lock Bars .....	35
Centre Key Lock (Access Both Sides) .....	35
Octopod Centre-Mounted Sliding Bar Key Lock .....	35
Talius Hanger Locks .....	35

### ■ Storm Bars .....

.....	36
-------	----

### ■ Habitat Screen™ Bug Brush .....

.....	36
-------	----



TALIU<sup>®</sup>S



## SECURITY SOLUTIONS

### Product and Installation Specifications

#### **PART 1 - GENERAL**

- |     |   |  |
|-----|---|--|
| 1.1 | Related Work                            | .1 Related work to be determined by project architect or owner's representative.   |
| 1.2 | Scope of Work                           | <p>.1 The work of this section covers the supply and installation of rollshutters called for on the drawings and herein specified.</p> <p>.2 The Talius Authorized Dealer, or General Contractor, to provide all wood blocking and/or solid mounting surfaces required for a proper installation.</p> <p>.3 If required, the Talius Authorized Dealer, or General contractor, to provide and install all flashing for rollshutter panel boxes.</p> <p>.4 If required, the Talius Authorized Dealer, or General contractor, to provide and install exterior and/or interior finishing trim for the rollshutters</p> |
| 1.3 | Quality Assurance                       | <p>.1 <b>Approved Manufacturer:</b><br/> <b>TALIUS</b><br/> <b>Head Office: PO Box 3279, Salmon Arm, BC V1E 4S1</b><br/> <b>Tel: 250-832-7777</b><br/> <b>Fax: 250-832-8577</b><br/> <b>Website: www.talius.com</b><br/> <b>E-mail: info@talius.com</b></p>  |
| 1.4 | Submittals                              | <p>.1 Shop drawings: submit shop drawings showing details of rollshutters including curtains, guide rails, panel box housing, operators and other relevant hardware.</p> <p>.2 Submit manufacturer's data sheets. Indicate specific rollshutter types, construction components, material finishes, and operators.</p> <p>.3 Rollshutters are detailed on architectural drawings as scheduled. Sizes shown are nominal and confirmation by field measurement is required.</p> <p>.4 Submit samples of standard colours.</p>   |
| 1.5 | Products Delivery, Handling and Storage | .1 Deliver materials to site in shipping crates and packing. Store off the ground on wood supports spaced to prevent damage. Store inside building under cover to prevent damage from weather or construction activities. Coordinate delivery with construction schedule to prevent loss or damage.  |
| 1.6 | Operation and Maintenance               | .1 Rollshutters are to be of maintenance free design.  |
| 1.7 | Guarantee                               | .1 Manufacturer to provide a written warranty that all components are guaranteed against defects in material, design and workmanship for one year from date of installation for commercial and institutional installations and five years from the date of installation for residential installations. Installer to provide written guarantee that there will be no labour charge for warranty repairs for one year from date of installation.   |

#### **PART 2 - PRODUCTS**

- |     |              |   |
|-----|--------------|---|
| 2.1 | Rollshutters | <p>.1 <b>The Rollshutter curtain:</b><br/> The rollshutter curtain is to be made from individual roll formed aluminum profiles with an injected super-hard resin foam core and shall have a cover width of 38 mm (1 1/2") and a thickness of 9 mm (11/32"). Minimum aluminum gauge to be 0.62 mm (0.0244"). Finish to be baked-on enamel with a dry film thickness of at least 0.05 mm (0.0020"). The minimum weight per square metre is to be 8.0 kg (0.0114 lbs/inch<sup>2</sup>).<br/> Manufacturer's description: <b>SAFE MINI.</b></p> |
|-----|--------------|---|

## **PART 2 - PRODUCTS**

(continued)

### **.2 Guide Rails:**

The guide rails are to be minimum 0.065" or 1.60 mm gauge aluminum extrusions fitted with two noise and weather insulating strips. All guide rails must have undergone a multiple stage pre-treatment procedure and be painted with a baked-on paint. Guide rails to be acid, alkali and oil resistant. The guide rail is to be made of two snap-together parts that prevent unauthorized access to the mounting screws. Curtain penetration into the guide rail shall be at least 41 mm (1 5/8") for sections less than 1.83 m (72") in width and at least 66 mm (2 5/8") for sections over 1.83 m (72") in width. Manufacturer's description: **SAFE RAIL**, and **SAFE-40 RAIL** respectively.

On rollshutter sections where width dimensions exceed 3.05 m (120"), split the rollshutter into two or more sections by means of a centre guide rail(s).

Manufacturer's description: **SAFE CENTRE RAIL**.

### **.3 Sill:**

If applicable, provide a 30 mm x 47 mm (1 1/8" x 1 13/16") U-shaped aluminum sill to hold the curtain securely in place when closed. Manufacturer's description: **SAFE U-SILL**. Where the U-sill is exposed to weather, drill a minimum of two "weep" holes in the inside channel of the U-sill to allow for moisture drainage.

### **.4 Build-Up:**

If applicable, provide heavy-gauge aluminum build-up underneath the guide rails, along the panel box top, panel box bottom, and sill. Unless otherwise specified, the width of the build-up is to be 35 mm (1 3/8"), depth to be suitable to provide obstruction-free operation of the rollshutter curtain.

### **.5 Panel Box Housing:**

Panel boxes are to be precision roll formed from 1.0 - 1.2 mm (0.040" - 0.0472") aluminum with an electro-statically bonded and baked finish. Lower half of the panel box must be detachable for future servicing access. Panel box service lid to be secured with tamper-proof security screws on all panel boxes below 2.13m (7') off the ground. All panels to be delivered to jobsite covered with protective, adhesive plastic film to prevent scratching. The protective film is to be removed by installer after job completion. All panel box endplates to be manufactured by pressure die-casting procedure from high grade aluminum alloy. Endplates must be chromed and laminated with a resistant PVC surface. The panel box style to be 5-corner. Panel box sizes to suit Rollshutters dimensions.

### **.6 Colour Selections:**

Unless otherwise indicated, items to be selected from manufacturer's standard colour range: white, beige, brown, black and silver.

- rollshutter curtain
- rollshutter curtain bottom profile
- guide rails
- sill
- aluminum build-up
- panel box housing

### **.7 Operation:**

Unless otherwise indicated, the Rollshutters shall be electrically operated. Provide a tubular 120 VAC motor installed inside the shaft. The motor unit shall be constructed with solenoid brakes, thermal overload protection switch with automatic reset and enclosed, permanently lubricated bearings and gears. All electrical components to

**PART 2 - PRODUCTS***(continued)*

be C.S.A. and U.L. certified. The motor unit shall be connected to a manual override control in order to operate the rollshutter in case of power failure. A metal pin extrusion shall be connected to a stainless steel universal joint at a downward angle of at least 45 degrees. A long handle crank of at least 1450mm made from anodized aluminum shall be connected to the universal joint on the operating person's side. The crank shall have two joints and a wall mounted clip for storing when not in use. Color of the crank rod to be silver.

Each motor unit shall be controlled by a momentary-contact, recessed, three position key switch. Switches to fit standard electrical boxes. Coverplates to be polished steel with one-way security screws. Locations as shown on drawings. The Wiring is per manufacturer's instructions and to local electrical code requirements. Supply and installation of electrical wiring (including drilling of wiring routing holes through mounting surfaces), mounting of supplied electrical switches, and the connection of all wiring to be performed by certified electricians.

**.8 Locking Devices:**

All rollshutters will be equipped with hanger locks constructed of corrosion resistant materials. Hanger locks are to be installed at sufficient intervals between shaft and curtain in order to prevent the curtains from being lifted by more than 40 mm (1 9/16") from the closed position, without the use of an operator. Talius hanger locks meet the requirements of European Standard EN 13659 and resist an upward force of 100 kg (220lbs).

**PART 3 – EXECUTION****3.1 Installation**

- .1 Rollshutters and hardware as described herein shall be installed by approved rollshutter installers. Installers must be factory authorized and installation must proceed in accordance with manufacturer's installation instructions.
- .2 The rollshutter contractor shall provide written confirmation before commencing installation that its Workers' Compensation Board account is currently active and in good standing, and that all of its employees working on site are covered by the rollshutter contractor's WCB account
- .3 The rollshutter contractor to supply and use suitable mounting hardware for the mounting surface application, including hollow-wall and concrete anchors, where necessary. Mounting hardware size to be a minimum of #8 x 2". Mounting hardware for the guide rails, build-up and U-sills to be installed between 20 cm – 30 cm (8" – 12") on centers. Mounting hardware for the panel box to be installed between 40 cm – 50 cm (16" – 20") on centers, horizontally along the top inside corner of the panel box, and each screw head to be supplemented with a large flat washer to avoid tearing through the sheet aluminum. Each cast aluminum end plate on a panel box to be secured with one fastener to the mounting surface, two if the rollshutter curtain weight exceeds 22 kg (50 lbs). When installation into brick or concrete surfaces is necessary, mounting hardware to be used shall be Tapcon style of suitable diameter and length.
- .4 Install Rollshutters plumb, true, square and level, free from distortion or defects affecting appearance or performance. Adjust and test moving parts to ensure smooth operation.
- .5 Suitable exterior caulking to be applied by the rollshutter contractor around the exterior perimeter of the completed rollshutter installation to prevent infiltration of moisture, wind and debris behind the rollshutter when the curtain is fully closed.
- .6 All work to be completed in a professional, safe and timely manner.

**PART 3 - EXECUTION**

**3.2 Clean-Up**

*(continued)*

- .1 As the work proceeds and upon completion, clean up and remove from the site all rubbish and packages. Leave all rollshutter and fixed panel parts clean.

**3.3 Schedule**

- .1 As per the Jobsite Specification Addendum.

## STORM PROTECTION

### Product and Installation Specifications

#### **PART 1 - GENERAL**

##### **1.1 Related Work**

- .1 Related work to be determined by project architect or owner's representative.

##### **1.2 Scope of Work**

- .1 The work of this section covers the supply and installation of rollshutters called for on the drawings and herein specified.
- .2 The Talius Authorized Dealer, or General Contractor, to provide all wood blocking and/or solid mounting surfaces required for a proper installation.
- .3 If required, the Talius Authorized Dealer, or General contractor, to provide and install all flashing for rollshutter panel boxes.
- .4 If required, the Talius Authorized Dealer, or General contractor, to provide and install exterior and/or interior finishing trim for the rollshutters

##### **1.3 Quality Assurance**

- .1 **Approved Manufacturer:**  
**TALIUS**  
**Head Office: PO Box 3279, Salmon Arm, BC V1E 4S1**  
**Tel: 250-832-7777**  
**Fax: 250-832-8577**  
**Website: www.talius.com**  
**E-mail: info@talius.com**

##### **1.4 Submittals**

- .1 Shop drawings: submit shop drawings showing details of rollshutters including curtains, guide rails, panel box housing, operators and other relevant hardware.
- .2 Submit manufacturer's data sheets. Indicate specific rollshutter types, construction components, material finishes, and operators.
- .3 Rollshutters are detailed on architectural drawings as scheduled. Sizes shown are nominal and confirmation by field measurement is required.
- .4 Submit samples of standard colours.

##### **1.5 Products Delivery, Handling and Storage**

- .1 Deliver materials to site in shipping crates and packing. Store off the ground on wood supports spaced to prevent damage. Store inside building under cover to prevent damage from weather or construction activities. Coordinate delivery with construction schedule to prevent loss or damage.

##### **1.6 Operation and Maintenance**

- .1 Rollshutters are to be of maintenance free design.

##### **1.7 Guarantee**

- .1 Manufacturer to provide a written warranty that all components are guaranteed against defects in material, design and workmanship for one year from date of installation for commercial and institutional installations and five years from the date of installation for residential installations. Installer to provide written guarantee that there will be no labour charge for warranty repairs for one year from date of installation.

#### **PART 2 - PRODUCTS**

##### **2.1 Rollshutters**

###### **.1 The Rollshutter curtain:**

The rollshutter curtain is to be made from individual roll formed aluminum profiles with an injected super-hard resin foam core and shall have a cover width of 38 mm (1 1/2") and a thickness of 9 mm (11/32"). Minimum aluminum gauge to be 0.62 mm (0.0244"). Finish to be baked-on enamel with a dry film thickness of at least 0.05 mm (0.0020"). The minimum weight per square metre is to be 8.0 kg (0.0114 lbs/inch<sup>2</sup>). Manufacturer's description: **SAFE MINI**.

## PART 2 - PRODUCTS

(continued)

### .2 Guide Rails:

The guide rails are to be minimum 0.065" or 1.60 mm gauge aluminum extrusions fitted with two noise and weather insulating strips. All guide rails must have undergone a multiple stage pre-treatment procedure and be painted with a baked-on paint. Guide rails to be acid, alkali and oil resistant. The guide rail is to be made of two snap-together parts that prevent unauthorized access to the mounting screws. Curtain penetration into the guide rail shall be at least 41 mm (1 5/8") for sections less than 1.83 m (72") in width and at least 66 mm (2 5/8") for sections over 1.83 m (72") in width. Manufacturer's description: **SAFE RAIL**, and **SAFE-40 RAIL** respectively.

On rollshutter sections where width dimensions exceed 3.05 m (120"), split the rollshutter into two or more sections by means of a centre guide rail(s). Manufacturer's description: **SAFE CENTRE RAIL**.

### .3 Sill:

If applicable, provide a 30 mm x 47 mm (1 1/8" x 1 13/16") U-shaped aluminum sill to hold the curtain securely in place when closed. Manufacturer's description: **SAFE U-SILL**. Where the U-sill is exposed to weather, drill a minimum of two "weep" holes in the inside channel of the U-sill to allow for moisture drainage.

### .4 Build-Up:

If applicable, provide heavy-gauge aluminum build-up underneath the guide rails, along the panel box top, panel box bottom, and sill. Unless otherwise specified, the width of the build-up is to be 35 mm (1 3/8"), depth to be suitable to provide obstruction-free operation of the rollshutter curtain.

### .5 Panel Box Housing:

Panel boxes are to be precision roll formed from 1.0 - 1.2 mm (0.040" - 0.0472") aluminum with an electro-statically bonded and baked finish. Lower half of the panel box must be detachable for future servicing access. Panel box service lid to be secured with tamper-proof security screws on all panel boxes below 2.13m (7') off the ground. All panels to be delivered to jobsite covered with protective, adhesive plastic film to prevent scratching. The protective film is to be removed by installer after job completion. All panel box endplates to be manufactured by pressure die-casting procedure from high grade aluminum alloy. Endplates must be chromed and laminated with a resistant PVC surface. The panel box style to be 5-corner. Panel box sizes to suit Rollshutters dimensions.

### .6 Colour Selections:

Unless otherwise indicated, items to be selected from manufacturer's standard colour range: white, beige, brown, black and silver.

- rollshutter curtain
- rollshutter curtain bottom profile
- guide rails
- sill
- aluminum build-up
- panel box housing

### .7 Operation:

Unless otherwise indicated, the Rollshutters shall be electrically operated. Provide a tubular 120 VAC motor installed inside the shaft. The motor unit shall be constructed with solenoid brakes, thermal overload protection switch with automatic reset and enclosed, permanently lubricated bearings and gears. All electrical components to be C.S.A. and U.L. certified.



**PART 2 - PRODUCTS***(continued)*

Each motor unit shall be controlled by a momentary-contact, recessed, three position paddle switch. The switches are to fit standard electrical boxes. Switch locations as shown on drawings. The Wiring is per manufacturer's instructions and to local electrical code requirements.

Supply and installation of electrical wiring (including drilling of wiring routing holes through mounting surfaces), mounting of supplied electrical switches, and the connection of all wiring to be performed by certified electricians.

**.8 Locking Devices:**

All rollshutters will be equipped with hanger locks constructed of corrosion resistant materials. Hanger locks are to be installed at sufficient intervals between shaft and curtain in order to prevent the curtains from being lifted by more than 40 mm (1 9/16") from the closed position, without the use of an operator. Talius hanger locks meet the requirements of European Standard EN 13659 and resist an upward force of 100 kg (220 lbs). Manufacturer's description: **HANGER LOCKS**

**.9 Storm Protection Device:**

All rollshutters will be equipped with one cross bar and one storm bar. The cross bar and storm bar are to be a minimum 5/32" or 4 mm gauge aluminum extrusions that have undergone multiple stage pre-treatment procedure and painted with baked on paint. Storm bar and cross bar to be acid, alkali and oil resistant. Manufacturer's description: **HEAVY DUTY STORM BAR**

**PART 3 – EXECUTION****3.1 Installation**

- .1 Rollshutters and hardware as described herein shall be installed by approved rollshutter installers. Installers must be factory authorized and installation must proceed in accordance with manufacturer's installation instructions.
- .2 The rollshutter contractor shall provide written confirmation before commencing installation that its Workers' Compensation Board account is currently active and in good standing, and that all of its employees working on site are covered by the rollshutter contractor's WCB account
- .3 The rollshutter contractor to supply and use suitable mounting hardware for the mounting surface application, including hollow-wall and concrete anchors, where necessary. Mounting hardware size to be a minimum of #8 x 2". Mounting hardware for the guide rails, build-up and U-sills to be installed between 20 cm – 30 cm (8" – 12") on centers. Mounting hardware for the panel box to be installed between 40 cm – 50 cm (16" – 20") on centers, horizontally along the top inside corner of the panel box, and each screw head to be supplemented with a large flat washer to avoid tearing through the sheet aluminum. Each cast aluminum end plate on a panel box to be secured with one fastener to the mounting surface, two if the rollshutter curtain weight exceeds 22 kg (50 lbs). When installation into brick or concrete surfaces is necessary, mounting hardware to be used shall be Tapcon style of suitable diameter and length.
- .4 Install Rollshutters plumb, true, square and level, free from distortion or defects affecting appearance or performance. Adjust and test moving parts to ensure smooth operation.

**PART 3 - EXECUTION**

(continued)

**3.2 Clean-Up**

- .5 Suitable exterior caulking to be applied by the rollshutter contractor around the exterior perimeter of the completed rollshutter installation to prevent infiltration of moisture, wind and debris behind the rollshutter when the curtain is fully closed.
  - .6 All work to be completed in a professional, safe and timely manner.
- .1 As the work proceeds and upon completion, clean up and remove from the site all rubbish and packages. Leave all rollshutter and Vandal Panels parts clean.

**3.3 Schedule**

- .1 As per the Jobsite Specification Addendum.

## SUN PROTECTION - HABITAT SCREENS™

### Product and Installation Specifications

#### **PART 1 - GENERAL**

##### **1.1 Related Work**

- .1 Related work to be determined by project architect or owner's representative.

##### **1.2 Scope of Work**

- .1 The work of this section covers the supply and installation of Habitat Screens called for on the drawings and herein specified.
- .2 The Talius Authorized Dealer, or General Contractor, to provide all wood blocking and/or solid mounting surfaces required for a proper installation.
- .3 If required, the Talius Authorized Dealer, or General contractor, to provide and install all flashing for Habitat Screen panel boxes.
- .4 If required, the Talius Authorized Dealer, or General contractor, to provide and install exterior and/or interior finishing trim for the Habitat Screens™.

##### **1.3 Quality Assurance**

- .1 **Approved Manufacturer:**  
**TALIUS**  
**Head Office: PO Box 3279, Salmon Arm, BC V1E 4S1**  
**Tel: 250-832-7777**  
**Fax: 250-832-8577**  
**Website: www.talius.com**  
**E-mail: info@talius.com**

##### **1.4 Submittals**

- .1 Shop drawings: submit shop drawings showing details of Habitat Screens including Thermoscreen material, guide rails, panel box housing, operators and other relevant hardware.
- .2 Submit manufacturer's data sheets. Indicate specific Habitat Screen types, construction components material finishes and operators.
- .3 Habitat Screens™ are detailed on architectural drawings as scheduled. Sizes shown are nominal and confirmation by field measurement is required..
- .4 Submit samples of standard colours.

##### **1.5 Products Delivery, Handling and Storage**

- .1 Deliver materials to site in shipping crates and packing. Store off the ground on wood supports spaced to prevent damage. Store inside building under cover to prevent damage from weather or construction activities. Coordinate delivery with construction schedule to prevent loss or damage.

##### **1.6 Operation and Maintenance**

- .1 Habitat Screens™ are to be of maintenance free design.

##### **1.7 Guarantee**

- .1 Manufacturer to provide a written warranty that all components are guaranteed against defects in material, design and workmanship for one year from date of installation for commercial and institutional installations and five years from the date of installation for residential installations. Installer to provide written guarantee that there will be no labour charge for warranty repairs for one year from date of installation.

#### **PART 2 - PRODUCTS**

##### **2.1 Habitat Screens**

##### **.1 The Habitat Screen curtain:**

The Habitat Screen curtain is to be made from exterior, vinyl-coated polyester roller shade fabric, with a 28% polyester, 72% vinyl on polyester composition. The openness factor (O-F) is approximately 5%. The weight of the curtain is to be 522 g/m<sup>2</sup>, 0.000742 lbs/inch<sup>2</sup>, or 15.4 oz/yd<sup>2</sup>. The thickness of the Habitat Screen curtain is to be 0.74 mm, 0.029 inch. The breaking strength of the Habitat Screen curtain is warp: 350 lbs/inch and fill: 235 lbs/inch. Each side of the Habitat Screen curtain must feature a #4.5 Coil

## **PART 2 - PRODUCTS**

(continued)

zipper attached via heat weldable film and welding process. Standard fabric roll widths of 126", to minimize visible seams. Horizontal seaming of screen material is required when the height and width of the Habitat Screen exceeds the size of the fabric roll width.

Fire classification for Habitat Screen Fabric is:

- California Technical Bulletin 117 Sec. E. (CS-191-53)
- NFPA 101 (Class A Rating)
- IBC Section 903.1 (Class A Rating)

Manufacturer's description: **SUNTEX® 95.**

### **.2 Guide Rails:**

The guide rails are to be heavy gauge aluminum extrusions fitted with a PVC guide rail insert. All guide rails must have undergone a multiple stage chromate procedure and be painted with a baked-on paint. Guide rails to be acid, alkali and oil resistant. The guide rail is to include ¼", 6.5 mm build-up to incorporate slide-on Talius aluminum build-up. Curtain penetration into the guide rail shall be at least 26 mm (1"). Manufacturer's description: **HABITAT SCREEN PRO GUIDE RAIL WITH EDGE RETENTION INSERT.**

### **.3 Bottom Profile:**

The Habitat Screen™ Bottom Profile is to be made of two aluminum extrusions fitted together with a retaining channel for the screen fabric at the bottom. The extrusions are to be minimum 0.055" or 1.40 mm wall thickness and weighing 1.10 kg/lineal meter raw combined extrusion. The Bottom profile will be fitted with a weather insulating seal at the bottom. The Bottom Profile must allow for secure fitting of internal weight bars where required. The Bottom Profile must have undergone a multiple stage chromating procedure and be painted with baked-on paint. Bottom Profile to be acid, alkali, and oil resistant. The ends of the Bottom Profile must be capped off with a PVC caps.

### **.4 Sill:**

If applicable, provide a 22 mm x 42 mm (7/8" x 1 11/16") L-shaped aluminum sill for the Habitat Screen bottom profile to rest upon when closed. Manufacturer's description: **L-SILL.**

### **.5 Build-Up:**

If applicable, provide heavy-gauge aluminum build-up underneath the guide rails, along the panel box top, and panel box bottom. Unless otherwise specified, the width of the build-up is to be 35 mm (1 3/8"), depth to be suitable to provide obstruction-free operation of the habitat screen curtain.

### **.6 Panel Box Housing:**

Panel boxes are to be precision roll formed from 1.0 - 1.2 mm (0.040" - 0.0472") aluminum with an electro-statically bonded and baked finish. Lower half of the panel box must be detachable for future servicing access. Panel box service lid to be secured with tamper-proof security screws on all panel boxes below 2.13 m (7') off the ground. All panels to be delivered to jobsite covered with protective, adhesive plastic film to prevent scratching. The protective film is to be removed by installer after job completion. All panel box endplates to be manufactured by pressure die-casting

**PART 2 - PRODUCTS***(continued)*

procedure from high grade aluminum alloy. Endplates must be chromed and laminated with a resistant PVC surface. The panel box style to be 5-corner. Panel box size is 125 mm, or 5".

**.7 Colour Selections:**

Unless otherwise indicated, items to be selected from manufacturer's standard colour range: white, beige, brown, black and silver.

- Habitat Screen™ curtain
- Habitat Screen™ bottom profile
- guide rails
- sill
- aluminum build-up
- panel box housing.

**.8 Operation:**

Unless otherwise indicated, the Habitat Screens shall be electrically operated. Provide a tubular 120 VAC motor installed inside the shaft. The motor shall be constructed with an internal Radio Frequency Receiver and electronically programmable limits. The motor unit shall be constructed with solenoid brakes, thermal overload protection switch with automatic reset and enclosed, permanently lubricated bearings and gears. The motor shall be controlled wirelessly by a solar powered RTS Sun Sensor. For service and building maintenance by district staff: Exterior Solaris RTS remotes required to allow for individual shade control and to allow for turning on/off sun sensors, to accommodate service and building maintenance needs.

All electrical components to be C.S.A. and U.L. certified.

The Wiring is per manufacturer's instructions and to local electrical code requirements.

Supply and installation of electrical wiring (including drilling of wiring routing holes through mounting surfaces), mounting of supplied electrical switches, and the connection of all wiring to be performed by the certified electricians.

**PART 3 – EXECUTION****3.1 Installation**

- .1 Habitat Screen and hardware as described herein shall be installed by approved Habitat Screen installers. Installers must be factory authorized and installation must proceed in accordance with manufacturer's installation instructions.
- .2 The Habitat Screen contractor shall provide written confirmation before commencing installation that its Workers' Compensation Board account is currently active and in good standing, and that all of its employees working on site are covered by the Habitat Screen contractor's WCB account.
- .3 The Habitat Screen contractor will supply and use mounting hardware suitable for the mounting surface application, including hollow-wall and concrete anchors when necessary. The mounting hardware size is to be a minimum of #8 x 2" Mounting hardware for the guide rails, build-up L-sills to be installed between 20 cm – 30 cm (8" – 12") on centres. The mounting hardware for the panel box to be installed between 40 cm – 50 cm (16" – 20") on centres, horizontally along the top inside corner of the panel box, and each screw head to be supplemented with a large flat washer to avoid tearing through the sheet aluminum. Each cast aluminum end plate on a panel box to be secured with one fastener to the mounting surface.

**PART 3 - EXECUTION**

(continued)

When installation into brick or concrete surfaces is necessary, mounting hardware to be used shall be Tapcon style of suitable diameter and length.

- .4 Install Habitat Screens plumb, true, square and level, free from distortion or defects affecting appearance or performance. Adjust and test moving parts to ensure smooth operation.
- .5 Suitable exterior caulking to be applied by the Habitat Screen contractor around the exterior perimeter of the completed Habitat Screen installation to prevent infiltration of moisture, wind and debris behind the Habitat Screen when the curtain is fully closed.
- .6 All work to be completed in a professional, safe and timely manner.

**3.2 Clean-Up**

- .1 As the work proceeds and upon completion, clean up and remove from the site all rubbish and packages. Leave all Habitat Screen and fixed panel parts clean.

**3.3 Schedule**

- .1 As per the Jobsite Specification Addendum.

## SUN PROTECTION - ROLLSHUTTERS

### Product and Installation Specifications

#### **PART 1 - GENERAL**

##### **1.1 Related Work**

- .1 Related work to be determined by project architect or owner's representative.

##### **1.2 Scope of Work**

- .1 The work of this section covers the supply and installation of rollshutters called for on the drawings and herein specified.
- .2 The Talius Authorized Dealer, or General Contractor, to provide all wood blocking and/or solid mounting surfaces required for a proper installation.
- .3 If required, the Talius Authorized Dealer, or General contractor, to provide and install all flashing for rollshutter panel boxes.
- .4 If required, the Talius Authorized Dealer, or General contractor, to provide and install exterior and/or interior finishing trim for the rollshutters

##### **1.3 Quality Assurance**

- .1 **Approved Manufacturer:**  
**TALIUS**  
**Head Office: PO Box 3279, Salmon Arm, BC V1E 4S1**  
**Tel: 250-832-7777**  
**Fax: 250-832-8577**  
**Website: www.talius.com**  
**E-mail: info@talius.com**

##### **1.4 Submittals**

- .1 Shop drawings: submit shop drawings showing details of rollshutters including curtains, guide rails, panel box housing, operators and other relevant hardware.
- .2 Submit manufacturer's data sheets. Indicate specific rollshutter types, construction components, material finishes, and operators.
- .3 Rollshutters are detailed on architectural drawings as scheduled. Sizes shown are nominal and confirmation by field measurement is required.
- .4 Submit samples of standard colours.

##### **1.5 Products Delivery, Handling and Storage**

- .1 Deliver materials to site in shipping crates and packing. Store off the ground on wood supports spaced to prevent damage. Store inside building under cover to prevent damage from weather or construction activities. Coordinate delivery with construction schedule to prevent loss or damage.

##### **1.6 Operation and Maintenance**

- .1 Rollshutters are to be of maintenance free design.

##### **1.7 Guarantee**

- .1 Manufacturer to provide a written warranty that all components are guaranteed against defects in material, design and workmanship for one year from date of installation for commercial and institutional installations and five years from the date of installation for residential installations. Installer to provide written guarantee that there will be no labour charge for warranty repairs for one year from date of installation.

#### **PART 2 - PRODUCTS**

##### **2.1 Rollshutters**

###### **.1 The Rollshutter curtain:**

The rollshutter curtain is to be made from individual roll formed aluminum profiles with an injected insulated hard foam core and shall have a cover width of 40 mm (1 9/16") and a thickness of 9 mm (11/32"). Minimum aluminum gauge to be 0.33 mm (0.0244"). Finish being a polyurethane/polyamide topcoat with a dry film thickness of at least 0.03mm. The minimum weight per square metre is to be 4.55 kg. Manufacturer's description: **SHIELD MINI.**

**PART 2 - PRODUCTS**

(continued)

**.2 Guide Rails:**

The guide rails are to be heavy gauge aluminum extrusions fitted with two noise and weather insulating strips. All guide rails must have undergone a multiple stage chromate procedure and be painted with a baked-on paint. Guide rails to be acid, alkali and oil resistant. The guide rail is to be made of two snap-together parts that prevent unauthorized access to the mounting screws. Curtain penetration into the guide rail shall be at least 40 mm (1 9/16"). Manufacturer's description: **SAFE-40 RAIL**.

On rollshutter sections where width dimensions exceed 3.05 m (120"), split the rollshutter into two or more sections by means of a centre guide rail(s). Manufacturer's description: **SAFE CENTRE RAIL**.

**.3 Sill:**

If applicable, provide a 30 mm x 47 mm (1 1/8" x 1 13/16") U-shaped aluminum sill to hold the curtain securely in place when closed. Manufacturer's description: **SAFE U-SILL**. Where the U-sill is exposed to weather, drill a minimum of two "weep" holes in the inside channel of the U-sill to allow for moisture drainage.

**.4 Build-Up:**

If applicable, provide heavy-gauge aluminum build-up underneath the guide rails, along the panel box top, panel box bottom, and sill. Unless otherwise specified, the width of the build-up is to be 35 mm (1 3/8"), depth to be suitable to provide obstruction-free operation of the rollshutter curtain.

**.5 Panel Box Housing:**

Panel boxes are to be precision roll formed from 1.0 - 1.2 mm (0.040" - 0.0472") aluminum with an electro-statically bonded and baked finish. Lower half of the panel box must be detachable for future servicing access. Panel box service lid to be secured with tamper-proof security screws on all panel boxes below 2.13m (7') off the ground. All panels to be delivered to jobsite covered with protective, adhesive plastic film to prevent scratching. The protective film is to be removed by installer after job completion. All panel box endplates to be manufactured by pressure die-casting procedure from high grade aluminum alloy. Endplates must be chromed and laminated with a resistant PVC surface. The panel box style to be 5-corner. Panel box sizes to suit Rollshutters dimensions.

**.6 Colour Selections:**

Unless otherwise indicated, items to be selected from manufacturer's standard colour range: white, beige, brown, black and silver.

- rollshutter curtain
- rollshutter curtain bottom profile
- guide rails
- sill
- aluminum build-up
- panel box housing

**.7 Operation:**

Unless otherwise indicated, the Rollshutters shall be electrically operated. Provide a tubular 120 VAC motor installed inside the shaft. The motor unit shall be constructed with solenoid brakes, thermal overload protection switch with automatic reset and enclosed, permanently lubricated bearings and gears. All electrical components to be C.S.A. and U.L. certified. Each motor unit shall be controlled by a momentary-contact,



**PART 2 - PRODUCTS***(continued)*

three position toggle switch. The switches are to fit standard electrical boxes. Switch locations as shown on drawings. The Wiring is per manufacturer's instructions and to local electrical code requirements.

Supply and installation of electrical wiring (including drilling of wiring routing holes through mounting surfaces) mounting of supplied electrical switches, and the connection of all wiring to be performed by certified electricians.

**.8 Locking Devices:**

All rollshutters will be equipped with hanger locks constructed of corrosion resistant materials. Hanger locks are to be installed at sufficient intervals between shaft and curtain in order to prevent the curtains from being lifted by more than 40 mm (1 9/16") from the closed position, without the use of an operator. Talius hanger locks meet the requirements of European Standard EN 13659 and resist an upward force of 100 kg (220 lbs).

**PART 3 - EXECUTION****3.1 Installation**

- .1 Rollshutters and hardware as described herein shall be installed by approved rollshutter installers. Installers must be factory authorized and installation must proceed in accordance with manufacturer's installation instructions.
- .2 The rollshutter contractor shall provide written confirmation before commencing installation that its Workers' Compensation Board account is currently active and in good standing, and that all of its employees working on site are covered by the rollshutter contractor's WCB account
- .3 The rollshutter contractor to supply and use suitable mounting hardware for the mounting surface application, including hollow-wall and concrete anchors, where necessary. Mounting hardware size to be a minimum of #8 x 2". Mounting hardware for the guide rails, build-up and U-sills to be installed between 20 cm – 30 cm (8" – 12") on centers. Mounting hardware for the panel box to be installed between 40 cm – 50 cm (16" – 20") on centers, horizontally along the top inside corner of the panel box, and each screw head to be supplemented with a large flat washer to avoid tearing through the sheet aluminum. Each cast aluminum end plate on a panel box to be secured with one fastener to the mounting surface, two if the rollshutter curtain weight exceeds 22 kg (50 lbs). When installation into brick or concrete surfaces is necessary, mounting hardware to be used shall be Tapcon style of suitable diameter and length.
- .4 Install Rollshutters plumb, true, square and level, free from distortion or defects affecting appearance or performance. Adjust and test moving parts to ensure smooth operation.
- .5 Suitable exterior caulking to be applied by the rollshutter contractor around the exterior perimeter of the completed rollshutter installation to prevent infiltration of moisture, wind and debris behind the rollshutter when the curtain is fully closed.
- .6 All work to be completed in a professional, safe and timely manner.

**3.2 Clean-Up**

- .1 As the work proceeds and upon completion, clean up and remove from the site all rubbish and packages. Leave all rollshutter and fixed panel parts clean.

**3.3 Schedule**

- .1 As per the Jobsite Specification Addendum.



## ENERGY EFFICIENCY

### Product and Installation Specifications

#### **PART 1 - GENERAL**

##### **1.1 Related Work**

.1 Related work to be determined by project architect or owner's representative.

##### **1.2 Scope of Work**

- .1 The work of this section covers the supply and installation of rollshutters and/or habitat screens™ called for on the drawings and herein specified.
- .2 The Talius Authorized Dealer, or General Contractor, to provide all wood blocking and/or solid mounting surfaces required for a proper installation.
- .3 If required, the Talius Authorized Dealer, or General contractor, to provide and install all flashing for rollshutters and/or habitat screens panel boxes.
- .4 If required, the Talius Authorized Dealer, or General contractor, to provide and install exterior and/or interior finishing trim for the rollshutters and/or habitat screens™.

##### **1.3 Quality Assurance**

- .1 **Approved Manufacturer:**  
**TALIUS**  
**Head Office: PO Box 3279, Salmon Arm, BC V1E 4S1**  
**Tel: 250-832-7777**  
**Fax: 250-832-8577**  
**Website: www.talius.com**  
**E-mail: info@talius.com**

##### **1.4 Submittals**

- .1 Shop drawings: submit shop drawings showing details of rollshutters and/or habitat screens including curtains, guide rails, panel box housing, operators and other relevant hardware.
- .2 Submit manufacturer's data sheets. Indicate specific rollshutter and/or habitat screen™ types, construction components material finishes and operators.
- .3 Rollshutters and/or habitat screens™ are detailed on architectural drawings as scheduled. Sizes shown are nominal and confirmation by field measurement is required.
- .4 Submit samples of standard colours.

##### **1.5 Products Delivery, Handling and Storage**

- .1 Deliver materials to site in shipping crates and packing. Store off the ground on wood supports spaced to prevent damage. Store inside building under cover to prevent damage from weather or construction activities. Coordinate delivery with construction schedule to prevent loss or damage.

##### **1.6 Operation and Maintenance**

- .1 Rollshutters and/or habitat screens™ are to be of maintenance free design.

##### **1.7 Guarantee**

- .1 Manufacturer to provide a written warranty that all components are guaranteed against defects in material, design and workmanship for one year from date of installation for commercial and institutional installations and five years from the date of installation for residential installations. Installer to provide written guarantee that there will be no labour charge for warranty repairs for one year from date of installation.

#### **PART 2 - PRODUCTS**

##### **2.1 Rollshutters**

##### **.1 The Rollshutter curtain:**

The Rollshutter curtain is to be made from individual rollformed aluminum profiles with an injected insulated hard foam core and shall have a cover width of 40 mm and a thickness of 9.0 mm. The minimum aluminum gauge is to be 0.33 mm. Finish being a polyurethane/polyamide topcoat with a dry film thickness of at least 0.03 mm. The minimum weight per square metre is to be 4.55 kg. Manufacturer's description: **SHIELD MINI.**

**PART 2 - PRODUCTS***(continued)***.2 Guide Rails:**

The guide rails are to be heavy gauge aluminum extrusions fitted with two noise and weather insulating strips. All guide rails must have undergone a multiple stage chromate procedure and be painted with a baked-on paint. Guide rails to be acid, alkali and oil resistant. The guide rail is to be made of two snap-together parts that prevent unauthorized access to the mounting screws. Curtain penetration into the guide rail shall be at least 40 mm (1-9/16"). Manufacturer's description: **SAFE-40 RAIL**.

On Rollshutter sections where width dimensions exceed 3.05 m (120"), split the Rollshutter into two or more sections by means of a centre guide rail(s). Manufacturer's description: **SAFE CENTRE RAIL**.

**.3 Sill:**

If applicable, provide a 30 mm x 47 mm (1 1/8" x 1 13/16") U-shaped aluminum sill to hold the curtain securely in place when closed. Manufacturer's description: **SAFE U-SILL**. Where the U-sill is exposed to weather, drill a minimum of two "weep" holes in the inside channel of the U-sill to allow for moisture drainage.

**.4 Build-Up:**

If applicable, provide heavy-gauge aluminum build-up underneath the guide rails, along the panel box top, panel box bottom, and sill. Unless otherwise specified, the width of the build-up is to be 35mm (1-3/8"), depth to be suitable to provide obstruction free operation of the Rollshutter curtain.

**.5 Panel Box Housing:**

Panel boxes are to be precision rollformed from 1.0 – 1.2mm (0.040" – 0.0472") aluminum with an electro-statically bonded and baked finish. Lower half of the panel box must be detachable for future servicing access. Panel box service lid to be secured with tamper-proof security screws on all panel boxes below 2.13m (7') off the ground. All panels to be delivered to jobsite covered with protective, adhesive plastic film to prevent scratching. The protective film is to be removed by installer after job completion. All panel box endplates to be manufactured by pressure die-casting procedure from high grade aluminum alloy. Endplates must be chromed and laminated with a resistant PVC surface. The panel box style to be 5-corner. Panel box sizes to suit Rollshutters dimensions.

**.6 Colour Selections:**

Unless otherwise indicated, items to be selected from manufacturer's standard colour range: white, beige, brown, black and silver.

- rollshutter curtain
- rollshutter curtain bottom profile
- guide rails
- sill
- aluminum build-up
- panel box housing

**.7 Operation:**

Unless otherwise indicated, the Rollshutters shall be electrically operated. Provide a tubular 120 VAC motor installed inside the shaft. The motor unit shall be constructed with solenoid brakes, thermal overload protection switch with automatic reset and enclosed, permanently lubricated bearings and gears. All electrical components to be C.S.A. and U.L. certified. Each motor unit shall be controlled by a momentary-contact, three position toggle switch. The switches are to fit standard electrical boxes. Switch locations as shown on drawings. The Wiring is per manufacturer's instructions and to local electrical code requirements.

## **PART 2 - PRODUCTS**

### **2.2 Habitat Screens**

(continued)

Supply and installation of electrical wiring (including drilling of wiring routing holes through mounting surfaces) mounting of supplied electrical switches, and the connection of all wiring to be performed by certified electricians.

#### **.8 Locking Devices:**

All rollshutters will be equipped with hanger locks constructed of corrosion resistant materials. Hanger locks are to be installed at sufficient intervals between shaft and curtain in order to prevent the curtains from being lifted by more than 40 mm (1 9/16") from the closed position, without the use of an operator. Talius hanger locks meet the requirements of European Standard EN 13659 and resist an upward force of 100 kg (220 lbs).

#### **.1 The Habitat Screen curtain:**

The Habitat Screen curtain is to be made from exterior, vinyl-coated polyester roller shade fabric, with a 28% polyester, 72% vinyl on polyester composition. The openness factor (O-F) is approximately 5%. The weight of the curtain is to be 522 g/m<sup>2</sup>, 0.000742 lbs/inch<sup>2</sup>, or 15.4 oz/yd<sup>2</sup>. The thickness of the Habitat Screen curtain is to be 0.74 mm, 0.029 inch. The breaking strength of the Habitat Screen curtain is warp: 350 lbs/inch and fill: 235 lbs/inch. Each side of the Habitat Screen curtain must feature a #4.5 Coil zipper attached via heat weldable film and welding process. Standard fabric roll widths of 126", to minimize visible seams. Horizontal seaming of screen material is required when the height and width of the Habitat Screen exceeds the size of the fabric roll width.

Fire classification for Habitat Screen Fabric is:

- California Technical Bulletin 117 Sec. E. (CS-191-53)
- NFPA 101 (Class A Rating)
- IBC Section 903.1 (Class A Rating)

Manufacturer's description: **SUNTEX® 95.**

#### **.2 Guide Rails:**

The guide rails are to be heavy gauge aluminum extrusions fitted with a PVC guide rail insert. All guide rails must have undergone a multiple stage chromate procedure and be painted with a baked-on paint. Guide rails to be acid, alkali and oil resistant. The guide rail is to include 1/4", 6.5 mm build-up to incorporate slide-on Talius aluminum build-up. Curtain penetration into the guide rail shall be at least 26 mm (1"). Manufacturer's description: **HABITAT SCREEN PRO GUIDE RAIL WITH EDGE RETENTION INSERT.**

#### **.3 Bottom Profile:**

The Habitat Screen™ Bottom Profile is to be made of two aluminum extrusions fitted together with a retaining channel for the screen fabric at the bottom. The extrusions are to be minimum 0.055" or 1.40 mm wall thickness and weighing 1.10 kg/lineal meter raw combined extrusion. The Bottom profile will be fitted with a weather insulating seal at the bottom. The Bottom Profile must allow for secure fitting of internal weight bars where required. The Bottom Profile must have undergone a multiple stage chromating procedure and be painted with baked-on paint. Bottom Profile to be acid, alkali, and oil resistant. The ends of the Bottom Profile must be capped off with a PVC caps.

**PART 2 - PRODUCTS***(continued)***.4 Sill:**

If applicable, provide a 22 mm x 42 mm (7/8" x 1-11/16") L-shaped aluminum sill for the Habitat Screen bottom profile to rest upon when closed. Manufacturer's description: **L-SILL**.

**.5 Build-Up:**

If applicable, provide heavy-gauge aluminum build-up underneath the guide rails, along the panel box top, and panel box bottom. Unless otherwise specified, the width of the build-up is to be 35 mm (1 3/8"), depth to be suitable to provide obstruction-free operation of the Habitat Screen curtain.

**.6 Panel Box Housing:**

Panel boxes are to be precision roll formed from 1.0 - 1.2 mm (0.040" - 0.0472") aluminum with an electro-statically bonded and baked finish. Lower half of the panel box must be detachable for future servicing access. Panel box service lid to be secured with tamper-proof security screws on all panel boxes below 2.13m (7') off the ground. All panels to be delivered to jobsite covered with protective, adhesive plastic film to prevent scratching. The protective film is to be removed by installer after job completion. All panel box endplates to be manufactured by pressure die-casting procedure from high grade aluminum alloy. Endplates must be chromed and laminated with a resistant PVC surface. The panel box style to be 5-corner. Panel box size is 125 mm, or 5".

**.7 Colour Selections:**

Unless otherwise indicated, items to be selected from manufacturer's standard colour range: white, beige, brown, black and silver.

- Habitat Screen™ curtain
- Habitat Screen™ bottom profile
- guide rails
- sill
- aluminum build-up
- panel box housing

**.8 Operation:**

Unless otherwise indicated, the Habitat Screens shall be electrically operated. Provide a tubular 120 VAC motor installed inside the shaft. The motor shall be constructed with an internal Radio Frequency

Receiver and electronically programmable limits. The motor unit shall be constructed with solenoid brakes, thermal overload protection switch with automatic reset and enclosed, permanently lubricated bearings and gears. The motor shall be controlled wirelessly by a solar powered RTS Sun Sensor. For service and building maintenance by district staff: Exterior Solaris RTS remotes required to allow for individual shade control and to allow for turning on/off sun sensors, to accommodate service and building maintenance needs.

All electrical components to be C.S.A. and U.L. certified.

The Wiring is per manufacturer's instructions and to local electrical code requirements.

Supply and installation of electrical wiring (including drilling of wiring routing holes through mounting surfaces), mounting of supplied electrical switches, and the connection of all wiring to be performed by the certified electricians.

## **PART 3 – EXECUTION**

### **3.1 Installation**

- .1 Rollshutters, Habitat Screen and hardware as described herein shall be installed by approved Habitat Screen installers. Installers must be factory authorized and installation must proceed in accordance with manufacturer's installation instructions.
- .2 The Rollshutter and Habitat Screen contractor shall provide written confirmation before commencing installation that its Workers' Compensation Board account is currently active and in good standing, and that all of its employees working on site are covered by the Habitat Screen contractor's WCB account.
- .3 The Rollshutter and Habitat Screen contractor will supply and use mounting hardware suitable for the mounting surface application, including hollow-wall and concrete anchors when necessary. The mounting hardware size is to be a minimum of #8 x 2" Mounting hardware for the guide rails, build-up L-sills to be installed between 20 cm – 30 cm (8" – 12") on centres. The mounting hardware for the panel box to be installed between 40 cm – 50 cm (16" – 20") on centres, horizontally along the top inside corner of the panel box, and each screw head to be supplemented with a large flat washer to avoid tearing through the sheet aluminum. Each cast aluminum end plate on a panel box to be secured with one fastener to the mounting surface.

When installation into brick or concrete surfaces is necessary, mounting hardware to be used shall be Tapcon style of suitable diameter and length.

- .4 Install Rollshutters and/or Habitat Screens plumb, true, square and level, free from distortion or defects affecting appearance or performance. Adjust and test moving parts to ensure smooth operation.
- .5 Suitable exterior caulking to be applied by the Rollshutter and Habitat Screen contractor around the exterior perimeter of the completed Rollshutter and/or Habitat Screen installation to prevent infiltration of moisture, wind and debris behind the Habitat Screen when the curtain is fully closed.
- .6 All work to be completed in a professional, safe and timely manner.

### **3.2 Clean-Up**

- .1 As the work proceeds and upon completion, clean up and remove from the site all rubbish and packages. Leave all Rollshutter, Habitat Screen and fixed panel parts clean.

### **3.3 Schedule**

- .1 As per the Jobsite Specification Addendum.

## INSECT PROTECTION

### Product and Installation Specifications

#### **PART 1 - GENERAL**

##### **1.1 Related Work**

- .1 Related work to be determined by project architect or owner's representative.

##### **1.2 Scope of Work**

- .1 The work of this section covers the supply and installation of Habitat Screens™ called for on the drawings and herein specified.
- .2 The Talius Authorized Dealer, or General Contractor, to provide all wood blocking and/or solid mounting surfaces required for a proper installation.
- .3 If required, the Talius Authorized Dealer, or General contractor, to provide and install all flashing for Habitat Screen™ panel boxes.
- .4 If required, the Talius Authorized Dealer, or General contractor, to provide and install exterior and/or interior finishing trim for the Habitat Screens™.

##### **1.3 Quality Assurance**

- .1 **Approved Manufacturer:**  
**TALIUS**  
**Head Office: PO Box 3279, Salmon Arm, BC V1E 4S1**  
**Tel: 250-832-7777**  
**Fax: 250-832-8577**  
**Website: www.talius.com**  
**E-mail: info@talius.com**

##### **1.4 Submittals**

- .1 Shop drawings: submit shop drawings showing details of Habitat Screens including Thermoscreen material, guide rails, panel box housing, operators and other relevant hardware.
- .2 Submit manufacturer's data sheets. Indicate specific Habitat Screen types, construction components material finishes and operators.
- .3 Habitat Screens™ are detailed on architectural drawings as scheduled. Sizes shown are nominal and confirmation by field measurement is required.
- .4 Submit samples of standard colours.

##### **1.5 Products Delivery, Handling and Storage**

- .1 Deliver materials to site in shipping crates and packing. Store off the ground on wood supports spaced to prevent damage. Store inside building under cover to prevent damage from weather or construction activities. Coordinate delivery with construction schedule to prevent loss or damage.

##### **1.6 Operation and Maintenance**

- .1 Habitat Screens™ are to be of maintenance free design.

##### **1.7 Guarantee**

- .1 Manufacturer to provide a written warranty that all components are guaranteed against defects in material, design and workmanship for one year from date of installation for commercial and institutional installations and five years from the date of installation for residential installations. Installer to provide written guarantee that there will be no labour charge for warranty repairs for one year from date of installation.

#### **PART 2 - PRODUCTS**

##### **2.1 Habitat Screens**

##### **.1 The Habitat Screen™ curtain:**

The Habitat Screen curtain is to be made from exterior, vinyl-coated polyester insect screening. The openness factor (O-F) is approximately 45%. The fabric is tear and

## **PART 2 - PRODUCTS**

(continued)

puncture resistant. The weight of the curtain is to be 283.5 g/m<sup>2</sup>, 0.000403 lbs/inch<sup>2</sup>, or 7.3 oz/yd<sup>2</sup>. The thickness of the Habitat Screen™ curtain is to be 0.686 mm, 0.027 inch. The breaking strength of the Habitat Screen™ curtain is warp: 140 lbs/inch and fill: 112 lbs/inch. Each side of the Habitat Screen curtain must feature a #4.5 coil zipper attached via heat weldable film and welding process. Standard fabric roll widths of 120", to minimize visible seams. Horizontal seaming of screen material is required when the height and width of the Habitat Screen™ exceeds the size of the fabric roll width. Manufacturer's description: **TuffScreen®**

### **.2 Guide Rails:**

The guide rails are to be heavy gauge aluminum extrusions fitted with a PVC guide rail insert. All guide rails must have undergone a multiple stage chromate procedure and be painted with a baked-on paint. Guide rails to be acid, alkali and oil resistant. The guide rail is to include ¼", 6.5 mm build-up to incorporate slide-on Talius aluminum build-up. Curtain penetration into the guide rail shall be at least 26 mm (1"). Manufacturer's description: **HABITAT SCREEN PRO GUIDE RAIL WITH EDGE RETENTION INSERT.**

### **.3 Bottom Profile:**

The Habitat Screen™ Bottom Profile is to be made of two aluminum extrusions fitted together with a retaining channel for the screen fabric at the bottom. The extrusions are to be minimum 0.055" or 1.40 mm wall thickness and weighing 1.10 kg/lineal meter raw combined extrusion. The Bottom profile will be fitted with a weather insulating seal at the bottom. The Bottom Profile must allow for secure fitting of internal weight bars where required. The Bottom Profile must have undergone a multiple stage chromating procedure and be painted with baked-on paint. Bottom Profile to be acid, alkali, and oil resistant. The ends of the Bottom Profile must be capped off with a PVC caps.

### **.4 Sill:**

If applicable, provide a 22 mm x 42 mm (7/8" x 1 11/16") L-shaped aluminum sill for the Habitat Screen bottom profile to rest upon when closed. Manufacturer's description: **L-SILL.**

### **.5 Build-Up:**

If applicable, provide heavy-gauge aluminum build-up underneath the guide rails, along the panel box top, and panel box bottom. Unless otherwise specified, the width of the build-up is to be 35 mm (1 3/8"), depth to be suitable to provide obstruction-free operation of the habitat screen curtain.

### **.6 Panel Box Housing:**

Panel boxes are to be precision roll formed from 1.0 - 1.2 mm (0.040" - 0.0472") aluminum with an electro-statically bonded and baked finish. Lower half of the panel box must be detachable for future servicing access. Panel box service lid to be secured with tamper-proof security screws on all panel boxes below 2.13 m (7') off the ground. All panels to be delivered to jobsite covered with protective, adhesive plastic film to prevent scratching. The protective film is to be removed by installer after job completion. All panel box endplates to be manufactured by pressure die-casting procedure from high grade aluminum alloy. Endplates must be chromed and laminated with a resistant PVC surface. The panel box style to be 5-corner. Panel box size is 125 mm, or 5".



**PART 2 - PRODUCTS***(continued)***.7 Colour Selections:**

Unless otherwise indicated, items to be selected from manufacturer's standard colour range: white, beige, brown, black and silver.

- Habitat Screen™ curtain
- Habitat Screen™ bottom profile
- guide rails
- sill
- aluminum build-up
- panel box housing

**.8 Operation:**

Unless otherwise indicated, the Habitat Screen™ shall be electrically operated. Provide a tubular 120 VAC motor installed inside the shaft. The motor shall be constructed with an internal Radio Frequency Receiver and electronically programmable limits. The motor unit shall be constructed with solenoid brakes, thermal overload protection switch with automatic reset and enclosed, permanently lubricated bearings and gears. The motor shall be controlled wirelessly.

All electrical components to be C.S.A. and U.L. certified. The Wiring is per manufacturer's instructions and to local electrical code requirements.

Supply and installation of electrical wiring (including drilling of wiring routing holes through mounting surfaces), mounting of supplied electrical switches, and the connection of all wiring to be performed by the certified electricians.

**.8 Bug Brush:**

The Habitat Screen bottom profile includes either 3/4" (19.05 mm) or 2" (50.8 mm) nylon slide in style bug brush along its length. The panel box includes a 1 1/2" (38.1 mm) nylon bug brush with aluminum extrusion installed along its length. Manufacturers description: **BUG BRUSH**

**PART 3 – EXECUTION****3.1 Installation**

- .1 Habitat Screen and hardware as described herein shall be installed by approved Habitat Screen installers. Installers must be factory authorized and installation must proceed in accordance with manufacturer's installation instructions.
- .2 The Habitat Screen contractor shall provide written confirmation before commencing installation that its Workers' Compensation Board account is currently active and in good standing, and that all of its employees working on site are covered by the Habitat Screen contractor's WCB account.
- .3 The Habitat Screen contractor will supply and use mounting hardware suitable for the mounting surface application, including hollow-wall and concrete anchors when necessary. The mounting hardware size is to be a minimum of #8 x 2" Mounting hardware for the guide rails, build-up L-sills to be installed between 20 cm – 30 cm (8" – 12") on centres. The mounting hardware for the panel box to be installed between 40 cm – 50 cm (16" – 20") on centres, horizontally along the top inside corner of the panel box, and each screw head to be supplemented with a large flat washer to avoid tearing through the sheet aluminum. Each cast aluminum end plate on a panel box to be secured with one fastener to the mounting surface.

When installation into brick or concrete surfaces is necessary, mounting hardware to be used shall be Tapcon style of suitable diameter and length.

**PART 3 - EXECUTION**

*(continued)*

**3.2 Clean-Up**

- .4 Install Habitat Screens plumb, true, square and level, free from distortion or defects affecting appearance or performance. Adjust and test moving parts to ensure smooth operation.
- .5 Suitable exterior caulking to be applied by the Habitat Screen contractor around the exterior perimeter of the completed Habitat Screen installation to prevent infiltration of moisture, wind and debris behind the Habitat Screen when the curtain is fully closed.
- .6 All work to be completed in a professional, safe and timely manner.

**3.3 Schedule**

- .1 As the work proceeds and upon completion, clean up and remove from the site all rubbish and packages. Leave all Habitat Screen and fixed panel parts clean.
- .1 As per the Jobsite Specification Addendum.

## VANDALISM PROTECTION

### Product and Installation Specifications

#### **PART 1 - GENERAL**

##### 1.1 Related Work

- .1 Related work to be determined by project architect or owner's representative.

##### 1.2 Scope of Work

- .1 The work of this section covers the supply and installation of rollshutters called for on the drawings and herein specified.
- .2 The Talius Authorized Dealer, or General Contractor, to provide all wood blocking and/or solid mounting surfaces required for a proper installation.
- .3 If required, the Talius Authorized Dealer, or General contractor, to provide and install all flashing for rollshutter panel boxes.
- .4 If required, the Talius Authorized Dealer, or General contractor, to provide and install exterior and/or interior finishing trim for the rollshutters

##### 1.3 Quality Assurance

- .1 **Approved Manufacturer:**  
**TALIUS**  
**Head Office: PO Box 3279, Salmon Arm, BC V1E 4S1**  
**Tel: 250-832-7777**  
**Fax: 250-832-8577**  
**Website: www.talius.com**  
**E-mail: info@talius.com**

##### 1.4 Submittals

- .1 Shop drawings: submit shop drawings showing details of rollshutters including curtains, guide rails, panel box housing, operators and other relevant hardware.
- .2 Submit manufacturer's data sheets. Indicate specific rollshutter types, construction components, material finishes, and operators.
- .3 Rollshutters are detailed on architectural drawings as scheduled. Sizes shown are nominal and confirmation by field measurement is required.
- .4 Submit samples of standard colours.

##### 1.5 Products Delivery, Handling and Storage

- .1 Deliver materials to site in shipping crates and packing. Store off the ground on wood supports spaced to prevent damage. Store inside building under cover to prevent damage from weather or construction activities. Coordinate delivery with construction schedule to prevent loss or damage.

##### 1.6 Operation and Maintenance

- .1 Rollshutters are to be of maintenance free design.

##### 1.7 Guarantee

- .1 Manufacturer to provide a written warranty that all components are guaranteed against defects in material, design and workmanship for one year from date of installation for commercial and institutional installations and five years from the date of installation for residential installations. Installer to provide written guarantee that there will be no labour charge for warranty repairs for one year from date of installation.

#### **PART 2 - PRODUCTS**

##### 2.1 Rollshutters

##### .1 The Rollshutter curtain:

The Rollshutter curtain is to be made from individual rollformed aluminum profiles with an injected super-hard resin foam core and shall have a cover width of 38 mm and a thickness of 9 mm. Minimum aluminum gauge to be 0.62 mm. Finish to be baked-on enamel with a dry film thickness of at least 0.05 mm. The minimum weight per square metre to be 8.0 kg. Manufacturer's description: **SAFE MINI**.

**PART 2 - PRODUCTS**

(continued)

**.2 Guide Rails:**

The guide rails are to be minimum 0.065" or 1.60 mm gauge aluminum extrusions fitted with two noise and weather insulating strips. All guide rails must have undergone a multiple stage pretreatment procedure and be painted with a baked-on paint. Guide rails to be acid, alkali and oil resistant. The guide rail is to be made of two snap-together parts that prevent unauthorized access to the mounting screws. Curtain penetration into the guide rail shall be at least 41 mm (1 5/8") for sections less than 1.83 m (72") in width and at least 66 mm (2 5/8") for sections over 1.83 m (72") in width. Manufacturer's description: **SAFE RAIL**, and **SAFE-40 RAIL** respectively.

On rollshutter sections where width dimensions exceed 3.05m (120"), split the rollshutter into two or more sections by means of a centre guide rail(s).

Manufacturer's description: **SAFE CENTRE RAIL**.

**.3 Sill:**

If applicable, provide a 30 mm x 47 mm (1 1/8" x 1 13/16") U-shaped aluminum sill to hold the curtain securely in place when closed. Manufacturer's description: **SAFE U-SILL**. Where the U-sill is exposed to weather, drill a minimum of two "weep" holes in the inside channel of the U-sill to allow for moisture drainage.

**.4 Build-Up:**

If applicable, provide heavy-gauge aluminum build-up underneath the guide rails, along the panel box top, panel box bottom, and sill. Unless otherwise specified, the width of the build-up is to be 35 mm (1 3/8"), depth to be suitable to provide obstruction-free operation of the rollshutter curtain.

**.5 Panel Box Housing:**

Panel boxes are to be precision roll formed from 1.0 - 1.2 mm (0.040" - 0.0472") aluminum with an electro-statically bonded and baked finish. Lower half of the panel box must be detachable for future servicing access. Panel box service lid to be secured with tamper-proof security screws on all panel boxes below 2.13m (7') off the ground. All panels to be delivered to jobsite covered with protective, adhesive plastic film to prevent scratching. The protective film is to be removed by installer after job completion. All panel box endplates to be manufactured by pressure die-casting procedure from high grade aluminum alloy. Endplates must be chromed and laminated with a resistant PVC surface. The panel box style to be 5-corner. Panel box sizes to suit Rollshutters dimensions.

**.6 Colour Selections:**

Unless otherwise indicated, items to be selected from manufacturer's standard colour range: white, beige, brown, black and silver.

- rollshutter curtain
- rollshutter curtain bottom profile
- guide rails
- sill
- aluminum build-up
- panel box housing.

**.7 Operation:**

Unless otherwise indicated, the Rollshutters shall be electrically operated. Provide a tubular 120 VAC motor installed inside the shaft. The motor unit shall be constructed with solenoid brakes, thermal overload protection switch with automatic reset and

**PART 2 - PRODUCTS***(continued)*

enclosed, permanently lubricated bearings and gears. All electrical components to be C.S.A. and U.L. certified. The motor unit shall be connected to a manual over-ride control in order to operate the rollshutter in case of power failure. A metal pin extrusion shall be connected to a stainless steel universal joint at a downward angle of at least 45 degrees. A long handle crank of at least 1450mm made from anodized aluminum shall be connected to the universal joint on the operating person's side. The crank shall have two joints and a wall mounted clip for storing when not in use. Color of the crank rod to be silver.

Each motor unit shall be controlled by a momentary-contact, recessed, three position key switch. Switches to fit standard electrical boxes. Coverplates to be polished steel with one-way security screws. Locations as shown on drawings.

The Wiring is per manufacturer's instructions and to local electrical code requirements. Supply and installation of electrical wiring (including drilling of wiring routing holes through mounting surfaces), mounting of supplied electrical switches, and the connection of all wiring to be performed by certified electricians.

**.8 Locking Devices:**

All rollshutters will be equipped with hanger locks constructed of corrosion resistant materials. Hanger locks are to be installed at sufficient intervals between shaft and curtain in order to prevent the curtains from being lifted by more than 40 mm (1 9/16") from the closed position, without the use of an operator. Talius hanger locks meet the requirements of European Standard EN 13659 and resist an upward force of 100 kg (220 lbs).

**9. Anti-Graffiti Coating**

All Talius rollshutter curtains, guide rails, sills and panel boxes shall be coated with Talius non-sacrificial anti-graffiti coating designed to allow for easy clean-up of graffiti from the exposed rollshutter surfaces. Talius Anti-Graffiti coating is a modified aliphatic-polyurethane coating with enhanced abrasion resistance to provide resistance to chemicals, abrasions and impact. It is a clear coat that provides a gloss finish over stock and custom colors, and offers color retention and a non-stick surface. Anti-Graffiti coating is applied with a dry film thickness of 1.0 – 2.0 mils (25-50 microns). Hardness: ASTM D3363, 2H. Solvent Resistance: ASTM D4752, 100 MEK rubs; NO failure. Abrasion Resistance: 1000 cycles CS-17, ASTM D4060, 32 mg loss. Impact Resistance: ASTM D2794, 40 in lbs; NO failure. Flexibility: ASTM D522, 1/8" mandrel bend; NO failure.

**PART 3 – EXECUTION****3.1 Installation**

- .1 Rollshutters and hardware as described herein shall be installed by approved rollshutter installers. Installers must be factory authorized and installation must proceed in accordance with manufacturer's installation instructions.
- .2 The rollshutter contractor shall provide written confirmation before commencing installation that its Workers' Compensation Board account is currently active and in good standing, and that all of its employees working on site are covered by the rollshutter contractor's WCB account
- .3 The rollshutter contractor to supply and use suitable mounting hardware for the mounting surface application, including hollow-wall and concrete anchors, where necessary. Mounting hardware size to be a minimum of #8 x 2". Mounting hardware for the guide rails, build-up and U-sills to be installed between 20 cm – 30 cm (8" – 12") on centers. Mounting hardware for the panel box to be installed between 40 cm

**PART 3 - EXECUTION**

(continued)

– 50 cm (16" – 20") on centers, horizontally along the top inside corner of the panel box, and each screw head to be supplemented with a large flat washer to avoid tearing through the sheet aluminum. Each cast aluminum end plate on a panel box to be secured with one fastener to the mounting surface, two if the rollshutter curtain weight exceeds 22 kg (50 lbs). When installation into brick or concrete surfaces is necessary, mounting hardware to be used shall be Tapcon style of suitable diameter and length.

- .4 Install Rollshutters plumb, true, square and level, free from distortion or defects affecting appearance or performance. Adjust and test moving parts to ensure smooth operation.
- .5 Suitable exterior caulking to be applied by the rollshutter contractor around the exterior perimeter of the completed rollshutter installation to prevent infiltration of moisture, wind and debris behind the rollshutter when the curtain is fully closed.
- .6 All work to be completed in a professional, safe and timely manner.

**3.2 Clean-Up**

- .1 As the work proceeds and upon completion, clean up and remove from the site all rubbish and packages. Leave all rollshutter and fixed panel parts clean.

**3.3 Schedule**

- .1 As per the Jobsite Specification Addendum.